BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division

Revised Schedule - B

BBMP/2021-22/OW/WORK- INDENT50599

NAME OF WORK: Maintenance and Repairs of Borewell in Bagalagunte Ward No 14. - Call2

Sl. No	Description of work	Unit	Qty	Approved Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Providing, Rewinding of submersible pumpsets with copper insulation wire suitable gauge Including opening and refitting after repair, removal of submersible pumpset and refixing in position at work site with all labour lead lift all equipment, transportation as per instructions of Engineer incharge of work as per ISI specifiction with guarantee period of not less than 6 months	Job	14.00	5102.83	Rupees Five Thousand One Hundred Two and Eighty Three Paise Only
2	Providing, Rewinding of submersible pumpsets with copper insulation wire suitable gauge Including opening and refitting after repair, removal of submersible pumpset and refixing in position at work site with all labour lead lift all equipment, transportation as per instructions of Engineer incharge of work as per ISI specifiction with guarantee period of not less than 6 months	Job	6.00	5703.17	Rupees Five Thousand Seven Hundred Three and Seventeen Paise Only
3	Providing, Rewinding of submersible pumpsets with copper insulation wire suitable gauge Including opening and refitting after repair, removal of submersible pumpset and refixing in position at work site with all labour lead lift all equipment, transportation as per instructions of Engineer incharge of work as per ISI specifiction with guarantee period of not less than 6 months	Job	8.00	6453.58	Rupees Six Thousand Four Hundred Fifty Three and Fifty Eight Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Sl. No	Description of work	Unit	Qty	Approved Rat	
				In Figures (Rs.)	In Word
4	Replacing of pump parts. The following main componenets of submersible pumpsets requirng replacements as per ISI specifiction with guarantee period of not less than 12 months	Each	150.00	870.48	Rupees Eight Hundred Seventy and Forty Eight Paise Only
5	Replacing of pump parts. The following main componenets of submersible pumpsets requirng replacements as per ISI specifiction with guarantee period of not less than 12 months	Each	5.00	780.43	Rupees Seven Hundred Eighty and Forty Three Paise Only
6	Replacing of pump parts. The following main componenets of submersible pumpsets requirng replacements as per ISI specifiction with guarantee period of not less than 12 months	Each	150.00	183.32	Rupees One Hundred Eighty Three and Thirty Two Paise Only
7	Replacing of pump parts. The following main componenets of submersible pumpsets requirng replacements as per ISI specifiction with guarantee period of not less than 12 months	Each	150.00	183.32	Rupees One Hundred Eighty Three and Thirty Two Paise Only
8	Replacing of pump parts. The following main componenets of submersible pumpsets requirng replacements as per ISI specifiction with guarantee period of not less than 12 months	Each	10.00	482.41	Rupees Four Hundred Eighty Two and Forty One Paise Only
9	Replacing of pump parts. The following main componenets of submersible pumpsets requirng replacements as per ISI specifiction with guarantee period of not less than 12 months	Each	150.00	731.12	Rupees Seven Hundred Thirty One and Twelve Paise Only
10	Replacing of pump parts. The following main componenets of submersible pumpsets requirng replacements as per ISI specifiction with guarantee period of not less than 12 months	Each	10.00	686.10	Rupees Six Hundred Eighty Six and Ten Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

	Description of work	Unit	Qty	Approved Rates	
				In Figures (Rs.)	In Words (Rs.)
11	Replacing of pump parts. The following main componenets of submersible pumpsets requirng replacements as per ISI specifiction with guarantee period of not less than 12 months	Each	10.00	686.10	Rupees Six Hundred Eighty Six and Ten Paise Only
12	Replacing of pump parts. The following main componenets of submersible pumpsets requirng replacements as per ISI specifiction with guarantee period of not less than 12 months	Each	10.00	228.34	Rupees Two Hundred Twenty Eight and Thirty Four Paise Only
13	Replacing of pump parts. The following main componenets of submersible pumpsets requirng replacements as per ISI specifiction with guarantee period of not less than 12 months	Each	10.00	1103.11	Rupees One Thousand One Hundred Three and Eleven Paise Only
14	Replacing of pump parts. The following main componenets of submersible pumpsets requirng replacements as per ISI specifiction with guarantee period of not less than 12 months	Each	5.00	1103.11	Rupees One Thousand One Hundred Three and Eleven Paise Only
15	Replacing of pump parts. The following main componenets of submersible pumpsets requirng replacements as per ISI specifiction with guarantee period of not less than 12 months	Each	150.00	329.11	Rupees Three Hundred Twenty Nine and Eleven Paise Only
16	Replacing of pump parts. The following main componenets of submersible pumpsets requirng replacements as per ISI specifiction with guarantee period of not less than 12 months	Each	5.00	1775.27	Rupees One Thousand Seven Hundred Seventy Five and Twenty Seven Paise Only
17	Replacing of pump parts. The following main componenets of submersible pumpsets requirng replacements as per ISI specifiction with guarantee period of not less than 12 months	Each	10.00	337.69	Rupees Three Hundred Thirty Seven and Sixty Nine Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Sl. No	Description of work	Unit	Qty	Approved h...	
				In Figures (Rs.)	In Wo...
18	Replacing of pump parts. The following main componenets of submersible pumpsets requirng replacements as per ISI specifiction with guarantee period of not less than 12 months	Each	10.00	337.69	Rupees ... Hundre... Thirty Se... and Sixty N... Paise Only
19	Replacing of pump parts. The following main componenets of submersible pumpsets requirng replacements as per ISI specifiction with guarantee period of not less than 12 months	Each	5.00	309.81	Rupees Three Hundred Nine and Eighty One Paise Only
20	Replacing of pump parts. The following main componenets of submersible pumpsets requirng replacements as per ISI specifiction with guarantee period of not less than 12 months	Each	5.00	681.81	Rupees Six Hundred Eighty One and Eighty One Paise Only
21	Replacing of pump parts. The following main componenets of submersible pumpsets requirng replacements as per ISI specifiction with guarantee period of not less than 12 months	Each	5.00	525.29	Rupees Five Hundred Twenty Five and Twenty Nine Paise Only
22	Providing and Replacing of Rotor: as per ISI specifiction with guarantee period of not less than 12 months(	Each	10.00	428.81	Rupees Four Hundred Twenty Eight and Eighty One Paise Only
23	Providing and Replacing of Rotor: as per ISI specifiction with guarantee period of not less than 12 months	Each	10.00	428.81	Rupees Four Hundred Twenty Eight and Eighty One Paise Only
24	Providing and Replacing of Rotor: as per ISI specifiction with guarantee period of not less than 12 months	Each	10.00	165.09	Rupees One Hundred Sixty Five and Nine Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

	Description of work	Unit	Qty	Approved Rates	
				In Figures (Rs.)	In Words (Rs.)
25	Providing and Replacing of Carbon housing Thrust bearing block assembly complete with segment bearing pad & tip carbon/Ferradopadding pad	Each	10.00	1218.89	Rupees One Thousand Two Hundred Eighteen and Eighty Nine Paise Only
26	Providing and Replacing of Carbon housing Thrust bearing block assembly complete with segment bearing pad & tip carbon/Ferradopadding pad	Each	5.00	1415.07	Rupees One Thousand Four Hundred Fifteen and Seven Paise Only
27	Providing and Replacing of Carbon housing Thrust bearing block assembly complete with segment bearing pad & tip carbon/Ferradopadding pad(	Each	10.00	115.78	Rupees One Hundred Fifteen and Seventy Eight Paise Only
28	Providing and Replacing of Carbon housing Thrust bearing block assembly complete with segment bearing pad & tip carbon/Ferradopadding pad	Each	40.00	93.27	Rupees Ninety Three and Twenty Seven Paise Only
29	Providing and Replacing of Carbon housing Thrust bearing block assembly complete with segment bearing pad & tip carbon/Ferradopadding pad	Each	20.00	501.71	Rupees Five Hundred One and Seventy One Paise Only
30	Providing and Replacing of Carbon housing Thrust bearing block assembly complete with segment bearing pad & tip carbon/Ferradopadding pad	Each	10.00	64.32	Rupees Sixty Four and Thirty Two Paise Only
31	Providing and Replacing of Carbon housing Thrust bearing block assembly complete with segment bearing pad & tip carbon/Ferradopadding pad	Each	5.00	592.83	Rupees Five Hundred Ninety Two and Eighty Three Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Sl. No	Description of work	Unit	Qty	Approved Rate	
				In Figures (Rs.)	In Words
32	Providing and Replacing of Carbon housing Thrust bearing block assembly complete with segment bearing pad & tip carbon/Ferradopadding pad	Each	5.00	592.83	Rupees Five Hundred Ninety Two and Eighty Three Paise Only
33	Providing and Replacing of Carbon housing Thrust bearing block assembly complete with segment bearing pad & tip carbon/Ferradopadding pad	Each	5.00	1163.15	Rupees One Thousand One Hundred Sixty Three and Fifteen Paise Only
34	Providing and Replacing of Carbon housing Thrust bearing block assembly complete with segment bearing pad & tip carbon/Ferradopadding pad	Each	5.00	1834.23	Rupees One Thousand Eight Hundred Thirty Four and Twenty Three Paise Only
35	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts as per IS-694:1990.3C X 6.0Sq.mm	Rmtr	2320.00	213.36	Rupees Two Hundred Thirteen and Thirty Six Paise Only
36	Supplying and delivery at site brand new star/Essen/Lotus/Sun-Shines/Adarsh/ G.K.Controls Best Indigenous make combined energy meter-cum-control panel board unit minimum mechanically strong suitable for operation on 3HP 50HZ 380/440 Volts AC supply with spring loaded latch locking Device with a key Ribbs should be provided. contron panal board unit suitable for operation on 3HP 50HZ 380/440 Volts AC shall be consists Etc. complete the panal board shall be fabricated in single unit in the above components panal board suitable pump set 10HP to 20HP with stae delta starter out door panel board up to 20HP	No	4.00	22512.50	Rupees Twenty Two Thousand Five Hundred Twelve and Fifty Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

	Description of work	Unit	Qty	Approved Rates	
				In Figures (Rs.)	In Words (Rs.)
37	Fabricating Supplying and mounting MS Box of 16 SWG suitable for floor/ wall mounting fully weather proof with provision for better hear description, 9Providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamp with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 Sq cm	Sqcm	216000.00	0.36	Thirty Six Paise Only
38	Supplying and delivery of Submersible Pump Sets of 150mm dia suitable for bore well and confirming to IS 8034 specifications and its latest ammendments, 3-Phase, SS Bowl and impeller with low volt motor with testing as per instructions of Engineer incharge of work.15HP/11KV 35 STAGE	NO	2.00	72601.75	Rupees Seventy Two Thousand Six Hundred One and Seventy Five Paise Only
39	Labour charges for Erection, Electrification and commissioning of Pump sets, including aligning and balancing of all items including supply and erection of two pair of supporting clamps, bore well caps, cable clips and water tight gland cable protectors, bolts, nuts, valve and gauges,tools and equipments etc., involved in the job as per specifications, with necessary tests as per specifications, with testing of as per instructions of engineer incharge of work.(	No	42.00	6056.94	Rupees Six Thousand Fifty Six and Ninety Four Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Executive Engineer
Dasarahalli Division

Signature of the Contractor